

ANTIOCH CALIFORNIA OPPORTUNITY LIVES HERE

ADDENDUM NO. 2

TO
CONTRACT DOCUMENTS
FOR
MARCHETTI PARK RENOVATIONS
in
ANTIOCH, CALIFORNIA
P.W. 184-P8


ISSUED
July 31, 2024

This Addendum No. 2 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

SEE ATTACHED ADDENDUM ITEMS

Prepared By: _____

Scott Buenting, P.E.



BIDDER'S CERTIFICATION

I acknowledge receipt of this Addendum No. 2 and accept all conditions contained herein.

Bidder

By:

ADDENDUM NO. 2

**to
CONTRACT DOCUMENTS
for
MARCHETTI PARK RENOVATIONS
in
ANTIOCH, CALIFORNIA
P.W. 184-P8**

Issued July 31 2024

- 1) Sheet C1.0 notes that playground demolition is to be verified with the city. The scope of work for this area is to be completed by the City. Please disregard, this scope of work does not pertain to this project and will be completed by the City.
- 2) If the subcontractor owns or operates any off-road vehicle/diesel fueled vehicle that is not registerable/designed to be driven on a CA highway, the subcontractor is required to provide a CRC. The definition of vehicles that are subject to the CRC requirement is set forth in 13 CCR section 2449(b)(1) and (2).

If the subcontractor is stating that they do not have any vehicles subject to the CRC requirement, they should certify to that fact. The City can be penalized by CARB if the City knew/reasonably should have known that the subcontractor was required to comply. Thus, if a CRC is not being provided because the contractor is stating that a subcontractor does not require a CRC, we recommend obtaining and maintaining a certification from the subcontractor that the subcontractor does not intend to use any vehicles or equipment that are subject to California Code of Regulations Title 13, Section 2449(b).

(Note that a rented fleet is still subject to the requirements. Certification must be obtained from the rental company.)

Digital submission of CRC's within 48 hours of bid opening is acceptable.

- 3) Asphalt mix design shall be type B 1/4" maximum aggregate.
- 4) Sheet L1.1 shows an infield fines area, fines shall match existing infield in material and depth. Cultivated Turf edge at fines.
- 5) On sheet L2.1, keynote #5 requests removal/replacement of 7 existing valves of which the size is not available, assume 2" for the valves. Replace valves C-1 through C-8.
- 6) Disregard keynote #3, this is covered by keynote #5.
- 7) The scope for keynote #10 on sheet L2.1 follows as: Existing turf spray irrigation shall be adjusted at this location as required to conform to new LOW. Contractor shall field verify changes needed and ensure complete coverage is provided for turf area.
- 8) Sheet E3.1 shows new lighting inside the prefab restroom, the restroom shall be furnished with its own lighting interior and exterior.
- 9) No utility plans were provided regarding the (E) restroom and installation of the new pre-fab restroom. Sewer, water, and electrical connections are expected.

- 10) Sheet L2.1 shows an irrigation symbol not used on the irrigation legend (half filled triangle enclosed by circle) this symbol represents Hunter PROS-06-CV-MP3000-90.